

A.R.M. (US) Inc. 1506 Fernwood Dr. Wintersville, OH 43953 Telephone: (740) 264-6599 Fax: (740) 266-2953

Bulletin No.: SB090710 Release Date: 09/07/2010 Effective Date: 09/07/2010

Supersedes: NA

Completion Date: Immediately

Page: 1 of 5

SAFETY ALERT

RIDE MANUFACTURER: A.R.M. (US) Inc.

AFFECTED PRODUCTION DATES: July 2009 thru August 2010

RIDE NAME: Vertigo

AFFECTED SERIAL NO.(s): VG101-07-01-09, VG102-07-01-10, VG201-01-30-10, VG202-03-13-10

VG203-05-01-10, VG204-06-10-10, VG205-08-15-10

MODEL NUMBER(s): VG100 and VG200

ABSTRACT OF ISSUE: Improper Perimeter Fence Set Up / Shape

REASON FOR RELEASE:

Due to improper perimeter fence shape during operation, an incident involving a patron(s) riding in a swing seat has occurred. The patron(s) came into contact with the perimeter fence while the ride was still spinning as it came into the loading / unloading area.

ACTION TO BE TAKEN: (INSPECTION, MODIFICATION, REPLACEMENT, NDT, ORDER PARTS, MANUAL REVISION, PROCEDURAL CHANGE, ETC.)

It is imperative that the daily inspection of the perimeter fence shape and dimension be done as indicated in the ride manual and illustrated on the ride information tag to ensure passenger safety.


As an added safety measure, 6 additional perimeter fence sections are being added to increase the perimeter diameter to 76/ft. The number or fence panels shall increase from 28/pcs to 34 pcs. These additional sections will allow for a larger margin of error in set up due to issues such as, Set up error, and Daily inspection error and or uneven terrain.

Replacement of the existing ride information tag is necessary. New ride information tags are being printed and must be installed once received. Until this time, the illustrations provided on the following pages of this bulletin must be used.


Upon receipt of this bulletin please contact the parts department at 740-264-6599 Ext. 123 to provide a current shipping address.

DETAIL OF ISSUE:

Please note: Perimeter Fence Illustration and new Ride Information Tag on the following pages.



DETAIL OF ISSUE: Page 3 of 5 Vertigo 100 Illustration PASSENGER REQUIREMENTS MINIMUM HEIGHT MAX PASSENGERS MAX PASSENGERS MAX TOTAL PER TWO-DOSITION SEAT MAX TOTAL PER TWO-DOSITION SEAT MAX TOTAL PASSENGER LOAD MAX LOAD IMBALANCE TOWER/WING BOLT TORQUE HEIGHT



NOTICE

Only components specified, authorized, or provided by A.R.M. (US) INC. shall be used.

A.R.M. (US) INC. SPECIFICALLY DISCLAIMS ANY LIABILITY associated with the use of unauthorized components or modifications and/or alterations of authorized components.